

STAV'S HYDRAULIC SERVICES
ABN: 64 467 212 730
QBCC: 15061807
stephen@stavs.com.au
www.stavs.com.au
0402 303 599

SITE & SOIL EVALUATION REPORT 149 SANDY CREEK ROAD, BROMELTON

Prepared for: Beaudesert & Boonah Cranes

Prepared by: Stav's Hydraulic Services

Purpose: Site & Soil Evaluation Report

Issue No: A

Date Issued: 13-Oct-23

Author: Stephen Stavrinou

149 Sandy Creek Road, Bromelton Site & Soil Evaluation Report Rev:A | Date: 13-Oct-23

1. Contents

2.	Intro	3
3.	Executive summary	3
4.	Site Investigation	4
5.	Effluent Quality and Control Parameters	4
6.	Design Calculations	5
7.	Operation and Maintenance	7
8	Appendix A - Land application area plan.	8

149 Sandy Creek Road, Bromelton Site & Soil Evaluation Report

Rev:A | Date: 13-Oct-23

2. Intro

Stav's Hydraulic Services have carried out a Site and Soil Evaluation for the On-Site waste water treatment and the effluent disposal at Lot 3 on RP40309 - 149 Sandy Creek Road Bromelton, Qld.

The following report has been prepared in accordance with AS/NZS1547:2012, On-Site Domestic Waste Water Management and the Queensland Plumbing and Waste Water Code.

3. Executive summary

The recommendation and comments:

- 1. Use an Advanced Secondary all-waste sewage system such as the Envirocycle 10EP advanced Secondary Wastewater treatment system for the prosped sheds 1-4
- 2. Reuse the existing greywater pump out and black water septic systems for the existing residence
- 3. The peak daily design volume for the entire site is 9.2 Equivalent persons 1,380l/day loads from existing residence & proposed sheds 1 4.
- 4. Soil is a densely structured category 5 Clayey Sand, Low Plasticity, Fine Grained, yellow Design Irrigation Rate (DIR) = 21 mm / week
- 5. Total land application to be comprised of a land application area of 418m2 spread across 5 systems.
- 6. Have warning signs, complying with AS1319 at the boundaries of the designated area in two places and clearly visible to property users with wording such as "Recycled Water Avoid Contact DO NOT DRINK"
- 7. On-site sewage systems are not designed to cope with the flow from garbage grinders, fats, oils or chemicals and household cleaning products are to be used in accordance with their labels.
- 8. The land application area is an important area and has to be maintained e.g. regularly mowed, do not drive vehicles over the area or allow livestock to access the land application area Follow the maintenance requirements specified by the manufacturer and authorised service agent.

4. Site Investigation

Site Investigation				
Date of Investigation	20.09.2023			
Address	149 Sandy Creek Road Bromelton			
Area of Site	40,170m2			
Property Description	Lot 3 on RP40309			
Local Council	Scenic Rim Regional Council			
Weather	Fine			
Ground Cover	Grass			
Well/Bores	1			
Waterways	Nill			
Water Table	Nill			
Embankments	Nill			
Buildings	Existing Residence and sheds to western corner			
Site Exposure	Full Sunlight			
Boundaries	Sufficient			
Landscape Description	Waxing Divergent			
Diversion / Retention Mound	Nill			
Ground Water Cut off drains	Nill			
Intended Water Supply	Rain Water			

Soil Characteristics			
Depth	0-600mm		
Texture - structure - Colour	Silty Sand Loam in the top layers that increase in clay content with depth		
Soil Category	5		
Indicative permeability (Ksat) m/day	0.06		
Design Irrigation Rate (DIR) mm/week	21		
Design Loading Rate (DLR) mm/week	30		

5. Effluent Quality and Control Parameters

Effluent Quality Parameters				
Parameter	Primary	Secondary	Advanced Secondary	
Bod₅	120-240	20	10	
Total Suspended Solids (mg/L)	65-180	30	10	
Thermotolerant Coliforms (org/100mL)	N/A	200	10	

6. Design Calculations

Design Loadi	ngs - Existing Residence		
No. of Bedrooms	2		
Equivalent Persons (EP)	3		
Desing Flow L/day	60 Black Water only		
Daily flow / Weekly Flow	180 / 1260		
Design Loading Rate (DLR) mm/week	30		
Trench Area required (m²)	18 m²		
Trench Sizing	Adopt 2 trenches @ 15m long x 0.6m wide		
Design	Loadings - Shed 1		
No. of Staff	10		
Desing Flow L/day	30 Tank Water Supply		
Daily flow / Weekly Flow	300 / 2100		
Design Loading Rate (DIR) mm/week	21		
Land Application Area (m²)	100 m ² Adopt 100 m ²		
Design	Loadings - Shed 2		
No. of Staff	10		
Desing Flow L/day	30 Tank Water Supply		
Daily flow / Weekly Flow	300 / 2100		
Design Loading Rate (DIR) mm/week	21		
Land Application Area (m²)	100 m² Adopt 100 m²		
Design	Loadings - Shed 3		
No. of Staff	10		
Desing Flow L/day	30 Tank Water Supply		
Daily flow / Weekly Flow	300 / 2100		
Design Loading Rate (DIR) mm/week	21		
Land Application Area (m²)	100 m ² Adopt 100 m ²		
Design Loadings - Shed 4			
No. of Staff	10		
Desing Flow L/day	30 Tank Water Supply		
Daily flow / Weekly Flow	300 / 2100		
Design Loading Rate (DIR) mm/week	21		
Land Application Area (m²)	100 m ² Adopt 100 m ²		

TOTAL DESIG	GN	LOADINGS	FOR	SITE
Daily flow / Weekly Flow		1380	/	9660
Equivalent population			9.2	2

Rev:A | Date: 13-Oct-23

Bod5 Applied - Total Site			
Bod ₅ Applied 10mg / litre/ day	5.037 kg/year		
Soil Absorption Only	0.05kg / m² / year		
Minimum land Application Area	100.74 m ²		

The proposed wastewater system utilises an Advanced Secondary all-waste sewage treatment plant - Envirocycle 10EP advanced Secondary Wastewater treatment system for proposed sheds 1 -4

The Proposed systems will discharge to separate sprinklers as per below calculations.

Sprinkler Calculations - Sheds 1 - 4				
Sprinkler Zones Area	100	50	m² / sprinkler head	
No. Sprinklers	2.0	Sprinkler	heads	
Sprinkler radius	3.99	m		
Flow Rate Per Sprinkler Head		360	l/hour	
Pressure @ Sprinkler Head		68	kpa	
Effluent Flow Rate		720	L/hour	
Effluent Transfers	4	transfers@	7 minutes each	

The existing residence currently discharges to separate greywater pump out and and black water septic systems. These systems are proposed to remain as is with the exception of the black water trenches to be replaced with new in new location. 2

AS1547 states that:

- a. The effluent is required to be evenly distributed within the designated area.
- b. Have warning, complying with AS1319 at the boundaries of the designated area in two places and clearly visible to property users with wording such as "Recycled Water Avoid Contact DO NOT DRINK"
- c. Ensure that the effluent does not come into contact with people, domestic animals, fruit or vegetables for human consumption

149 Sandy Creek Road, Bromelton Site & Soil Evaluation Report

Rev:A | Date: 13-Oct-23

7. Operation and Maintenance

Maintenance requirements specified by the manufacturer and authorized service agent are to be implemented. These include:

- Use low sodium biodegradable soaps and detergents
- No paints, solvents, chemicals, food scraps, fats, oils or any other solids are not to be disposed of "down the drain"
- On-site sewage systems are not designed to cope with the flow from garbage grinders
- The land application area is an important area and has to be maintained e.g. regularly mowed or pruned also ensuring that there is no ponding of effluent in the disposal area
- Vehicles, livestock or general access is to be generally restricted with warning signs erected

149 Sandy Creek Road, Bromelton Site & Soil Evaluation Report Rev:A | Date: 13-Oct-23

8. Appendix A - Land application area plan

DESIGNER: STEPHEN STAVRINOU QBCC 15061807 ISSUE > 149 SANDY CREEK ROAD BROMELTON, QLD EFFLUENT DISPOSAL H103 - SITE PLAN EFFLUENT DISPOSAL LAYOUT H102 - LEGEND, NOTES & DETAILS H101 - COVER SHEET & LOCATION PLAN DRAWING LIST APPROVAL ISSUE AMENDMENT 13.10.2023 DATE CLIENT: BEAUDESERT & BOONAH CRANES PROJECT LOCATION CONSULTANT: HYDRAULIC NOT TO SCALE LOCATION PLAN 07 5623 4177 PROJECT: 149 SANDY CREEK ROAD LOT 3 ON RP40309 BROMELTON, QLD SANDY CREEK RD SANDY CREEK RD FLOOD RD **COVER SHEET & LOCATION PLAN** HYDRAULIC SERVICES SCALE / SIZE: PROJECT No. N.T.S @ A3 BBC1 - 6m H101 DRAWING No. ISSUE No. . 8m \triangleright 10m

BALL VALVE. 90° ELBOW. VALVE BOX. HEADER PIPE. SURFACE BOX. BOLT DOWN COUPLING FLEXIBLE HOSE

FLUSHING VALVE DETAIL

SCALE: NTS

'n

LOCATION OF EXISTING SERVICES HAS BEEN DETERMINED FROM SITE

5

REQUIREMENTS.

THESE PLANS SHALL BE READ IN CONJUNCTION WITH THE

APPROVED ARCHITECTURAL AND RELEVANT SERVICES PLANS AND

ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE

RELEVANT AUSTRALIAN STANDARDS AND THE LOCAL AUTHORITY REQUIREMENTS OF AS3500, THE BUILDING CODE OF AUSTRALIA

ALL EXPOSED HW & CW PIPEWORK SHALL BE COPPER TUBE TYPE "B" TO AS1432. CONNECT COPPER PIPE WITH BRAZED JOINTS IN AS1645 OR NECESSARY ALLOWANCES FOR THERMAL MOVEMENT OF PIPES SIMILAR. DENSO WRAP ALL CW PIPEWORK IN-GROUND. PROVIDE WATER SERVICES OR INSULATE WITH 'ARMAFLEX' INSULATION OR COMPRESSION JOINTS AS 1585. USE PRE-INSULATED PIPEWORK FOR HOT INSULATION TO ALL HOT WATER PIPEWORK. PROVIDE ALL

w

- 2 EXTERNAL TO BUILDING IN-GROUND MAY BE POLYETHYLENE PIPE OF MIN. CLASS 12, AND SHALL COMPLY WITH AS 1159. INSTALLATION OF POLYETHYLENE PIPES SHALL BE IN WATER SUPPLY PIPEWORK CONCEALED IN WALLS AND **SPECIFICATIONS** ACCORDANCE WITH AS 2033 AND THE MANUFACTURERS
- œ TAKE ALL NECESSARY PRECAUTIONS TO PREVENT WATER HAMMER AND RECTIFY SHOULD IT OCCUR

6.

PROVIDE INSTRUCTIONS MANUALS AT PRACTICAL COMPLETION.

'n

SUPERVISOR.

THE ENTIRE HYDRAULIC SERVICES INSTALLATION AND EQUIPMENT

SHALL BE MAINTAINED UNDER WARRANTY FOR A PERIOD OF

TWELVE (12) MONTHS AFTER PRACTICAL COMPLETION HAS BEEN

4

ARRANGE & APPLY TO THE LOCAL AUTHORITY FOR ALL

CHARGES, OBTAIN COMPLETION CERTIFICATE AND SUBMIT TO NECESSARY PERMITS. PAY ALL PLUMBING INSPECTION FEES AND THIS CONTRACTOR MUST CO-ORDINATE WITH ALL OTHER SERVICES. PIPEWORK SHOWN ON THIS DRAWING IS DIAGRAMMATIC ONLY. SUPERINTENDENT OF ANY DISCREPANCIES BEFORE PROCEEDING. SERVICES PRIOR TO COMMENCING CONSTRUCTION AND ADVISE THE HAS BEEN UNDERTAKEN. THE CONTRACTOR SHALL PROVE ALL VISITS AND EXISTING RECORD PLANS. NO PROVING OF SERVICES

FINAL LOCATION OF SERVICES SHALL BE DETERMINED ON SITE.

- 4. EXTERNAL AND INTERNAL HOSE COCKS SHALL BE FITTED WITH HOSE TYPE VACUUM BREAKERS
- 5 PROVIDE HW & CW STOPCOCKS TO ALL HW & CW FIXTURES
- 6 ALL PIPEWORK TO BE IDENTIFIED IN ACCORDANCE WITH AS1345
- 7. DIAMETERS UNLESS NOTED OTHERWISE. ALL PIPE DIAMETERS NOMINATED ARE NOMINAL BORE

ON SITE DISPOSAL NOTES

- IRRIGATION SYSTEM TO COMPLY WITH AS1547, QLD **SPECIFICATIONS** DOCUMENTATION AND MANUFACTURERS PLUMBING WASTE WATER CODE, ASSOCIATED
- ? MINIMUM COVER OVER RISING MAIN 450mm. RISING MAINS TO BE 32¢ PIPES TO AS/NZS 1477. PIPE TO BE LILAC COLORED AND/OR INSTALLED WITH TAPE IDENTIFYING THE PIPES CONTENTS AS SEWAGE
- PLANTED/SEEDED PRIOR TO THE COMMISSIONING OF THE SYSTEM TO ALLOW FOR PROPER EFFLUENT SHRUBS OR PLANTINGS. THE CHOSEN GRASS, TREATMENT OF THE REMAINING EFFLUENT RESIDUALS AS WELL AS PROVIDE NUTRIENT IRRIGATION SYSTEMS DISTRIBUTE EFFLUENT INTO SHRUBS OR PLANTINGS SHALL BE UPTAKE AND EVAPOTRANSPIRATION BY GRASS, THE TOPSOIL LAYERS TO PROVIDE IN-SOIL

- SANITARY DRAINAGE & VENT PIPEWORK IN UPVC IN MANUFACTURERS SPECIFICATIONS. ACCORDANCE WITH AS1260 AND THE
- ALL PIPEWORK TO BE IDENTIFIED IN ACCORDANCE WITH AS1345
- Ψ NOMINAL BORE DIAMETERS UNLESS NOTED OTHERWISE ALL PIPE DIAMETERS NOMINATED ARE

	R — R —	<u>LEGEND</u>
SANITARY DRAINAGE PIPEWORK	PUMPED EFFLUENT	

STORMWATER PIPEWORK VENT PIPEWORK

COLD WATER PIPEWORK HOT WATER PIPEWORK

X VALVE

BASIN CLEAR OUT TO SURFACE AUSTRALIAN HEIGHT DATUM COPPER PIPE CONDENSATE DRAIN ABOVE FINISHED FLOOR LEVEL

FFL CV CU FLOOR WASTE GULLY FINISHED FLOOR LEVEL EXISTING TO REMAIN DISHWASHER **JOWN PIPE**

CONTROL VALVE

COLD WATER

HOSE COCK c/w KEY OPERATED HANDLE (c/w REMOVABLE CHROME GRATE) HIGH LEVEL

INSPECTION CHAMBER HOT WATER HEATER HOT WATER

SHR SHR SHR SHR SHR SHR INSPECTION OPENING OVERFLOW RELIEF GULLY LOW LEVEL

SHOWER

WATER CLOSET /ACUUM BREAKER

13.10.2023 **BOONAH CRANES BEAUDESERT &**

ISSUE >

AMENDMENT

DATE

CLIENT:

APPROVAL ISSUE

FROM RELEVANT AUTHORITIES

COUNCIL INSPECTION REPORTS AND FINAL COMPLETION CERTIFICATES

- "AS CONSTRUCTED" DRAWINGS

INFORMATION FOR EACH ITEM OF EQUIPMENT

OPERATING AND MAINTENANCE INSTRUCTIONS AND WARRANTY

LISTING OF EQUIPMENT, MANUFACTURERS NAMES, AGENTS ETC.

- GENERAL DESCRIPTION OF PROJECT

CONTAINING THE FOLLOWING:

DESIGNER: STEPHEN STAVRINOU QBCC 15061807



shs@stavs.com.au PO Box 529,

07 5623 4177

PROJECT:

Jimboomba, Qld

www.stavs.com.au

BROMELTON, QLD LOT 3 ON RP40309

149 SANDY CREEK ROAD

- m TITLE: HYDRAULIC SERVICES _EGEND, NOTES & DETAILS 2m 4m 6m

m8

10m

SCALE / SIZE: PROJECT No. BBC H102 DRAWING No. ISSUE No. ➣

NTS @ A3

